

THE UNITED STATES OF AMERICA

TO ALL TO WHOM THESE PRESENTS SHALL COME:

**UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office**

December 22, 2003

**THIS IS TO CERTIFY THAT ANNEXED HERETO IS A TRUE COPY OF
THE BELOW IDENTIFIED INTERNATIONAL APPLICATION AS
ORIGINALLY FILED AND ANY CORRECTIONS THERETO FROM THE
RECORDS OF THE UNITED STATES PATENT AND TRADEMARK
OFFICE ACTING AS A RECEIVING OFFICE UNDER THE PATENT
COOPERATION TREATY.**

**APPLICATION NUMBER: *PCT/US00/19619*
FILING DATE: *July 19, 2000***



**By Authority of the
COMMISSIONER OF PATENTS AND TRADEMARKS**

T. Wallace
T. WALLACE
Certifying Officer

SEARCH COPY PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

PCT/US 00 / 19619

International Application No.

(19.07.00)

19 JUL 2000

International Filing Date

**PCT INTERNATIONAL
APPLICATION RO/US**

Name of receiving Office and PCT International Application*

Applicant's or agent's file reference

(if desired) (12 characters maximum) CM2399F/JH

Box No. I TITLE OF INVENTION

Cleaning Composition

Box No. II APPLICANT

Name and address:

THE PROCTER & GAMBLE COMPANY
One Procter & Gamble Plaza
Cincinnati, Ohio 45202
US

☐ This person is also inventor.

Telephone No.

513-627-7025

Facsimile No.

513-627-6333

Teleprinter No.

State (i.e. country) of nationality:

US

State (i.e. country) of residence:

US

This person is applicant
for the purposes of:

☒ all designated
states

☐ all designated States except
the United States of America

☐ the United States
of America only

☐ the States indicated in
the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address:

This person is:

☐ applicant only

☐ applicant and inventor

☐ inventor only (If this check-
box is marked, do not fill in below.)

State (i.e. country) of nationality:

State (i.e. country) of residence:

This person is applicant
for the purposes of:

☐ all designated
states

☐ all designated States except
the United States of America

☐ the United States
of America only

☐ the States indicated in
the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on
behalf of the applicant(s) before the competent International Authorities
as:

☒ agent
representative

☐ common

Name and address:

REED, T. David/HUGHETT, Eileen L.
The Procter & Gamble Company
5299 Spring Grove Avenue
Cincinnati, OH 45217-1087
US

Telephone No.

513-627-7025

Facsimile No.

513-627-6333

Teleprinter No.

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the
space

above is used instead to indicate a special address to which correspondence should be sent.

Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent


- ☐ **AP ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, MZ Mozambique, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☐ **EA Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP European Patent:** AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ **OA OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|---|---|
| <input type="checkbox"/> AE United Arab Emirates | <input type="checkbox"/> LC Saint Lucia |
| <input type="checkbox"/> AG Antigua and Barbuda | <input type="checkbox"/> LK Sri Lanka |
| <input type="checkbox"/> AL Albania | <input type="checkbox"/> LR Liberia |
| <input type="checkbox"/> AM Armenia | <input type="checkbox"/> LS Lesotho |
| <input type="checkbox"/> AT Austria and utility model | <input type="checkbox"/> LT Lithuania |
| <input type="checkbox"/> AU Australia | <input type="checkbox"/> LU Luxembourg |
| <input type="checkbox"/> AZ Azerbaijan | <input type="checkbox"/> LV Latvia |
| <input type="checkbox"/> BA Bosnia and Herzegovina | <input type="checkbox"/> MA Morocco |
| <input type="checkbox"/> BB Barbados | <input type="checkbox"/> MD Republic of Moldova |
| <input type="checkbox"/> BG Bulgaria | <input type="checkbox"/> MG Madagascar |
| <input type="checkbox"/> BR Brazil | <input type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input type="checkbox"/> BY Belarus | <input type="checkbox"/> MN Mongolia |
| <input type="checkbox"/> BZ Belize | <input type="checkbox"/> MW Malawi |
| <input type="checkbox"/> CA Canada | <input type="checkbox"/> MX Mexico |
| <input type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input type="checkbox"/> MZ Mozambique |
| <input type="checkbox"/> CN China | <input type="checkbox"/> NO Norway |
| <input type="checkbox"/> CR Costa Rica | <input type="checkbox"/> NZ New Zealand |
| <input type="checkbox"/> CU Cuba | <input type="checkbox"/> PL Poland |
| <input type="checkbox"/> CZ Czech Republic and utility model | <input type="checkbox"/> PT Portugal |
| <input type="checkbox"/> DE Germany and utility model | <input type="checkbox"/> RO Romania |
| <input type="checkbox"/> DK Denmark and utility model | <input type="checkbox"/> RU Russian Federation |
| <input type="checkbox"/> DM Dominica | <input type="checkbox"/> SD Sudan |
| <input type="checkbox"/> DZ Algeria | <input type="checkbox"/> SE Sweden |
| <input type="checkbox"/> EE Estonia and utility model | <input type="checkbox"/> SG Singapore |
| <input type="checkbox"/> ES Spain | <input type="checkbox"/> SI Slovenia |
| <input type="checkbox"/> FI Finland and utility model | <input type="checkbox"/> SK Slovakia and utility model |
| <input checked="" type="checkbox"/> GB United Kingdom | <input type="checkbox"/> SL Sierra Leone |
| <input type="checkbox"/> GD Grenada | <input type="checkbox"/> TJ Tajikistan |
| <input type="checkbox"/> GE Georgia | <input type="checkbox"/> TM Turkmenistan |
| <input type="checkbox"/> GH Ghana | <input type="checkbox"/> TR Turkey |
| <input type="checkbox"/> GM Gambia | <input type="checkbox"/> TT Trinidad and Tobago |
| <input type="checkbox"/> HR Croatia | <input type="checkbox"/> TZ United Republic of Tanzania |
| <input type="checkbox"/> HU Hungary | <input type="checkbox"/> UA Ukraine |
| <input type="checkbox"/> ID Indonesia | <input type="checkbox"/> UG Uganda |
| <input type="checkbox"/> IL Israel | <input type="checkbox"/> US United States of America |
| <input type="checkbox"/> IN India | <input type="checkbox"/> UZ Uzbekistan |
| <input type="checkbox"/> IS Iceland | <input type="checkbox"/> VN Viet Nam |
| <input type="checkbox"/> JP Japan | <input type="checkbox"/> YU Yugoslavia |
| <input type="checkbox"/> KE Kenya | <input type="checkbox"/> ZA South Africa |
| <input type="checkbox"/> KG Kyrgyzstan | <input type="checkbox"/> ZW Zimbabwe |
| <input type="checkbox"/> KP Democratic People's Republic of Korea | |
| <input type="checkbox"/> KR Republic of Korea and utility model | |
| <input type="checkbox"/> KZ Kazakhstan | |

Check-box reserved for designating States which have become party to the PCT after issuance of this sheet:

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation (including fees) must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM				
<input type="checkbox"/> Further priority claims are indicated in the Supplemental Box				
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application: regional Office	intl. application: receiving Office
item (1)				
item (2)				
item (3)				
<input type="checkbox"/> The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s): _____ *Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii). See Supplemental Box.				
Box No. VII INTERNATIONAL SEARCHING AUTHORITY				
Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):		Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):		
ISA/EP		Date (day/month/year) Number Country (or regional Office)		
Box No. VIII CHECK LIST: LANGUAGE OF FILING				
This international applications contains the following number of sheets:		This international application is accompanied by the item(s) marked below:		
request : 03		1. <input checked="" type="checkbox"/> fee calculation sheet		
description (excluding sequence listing part) : 30		2. <input type="checkbox"/> separate signed power(s) of attorney		
claims : 10		3. <input checked="" type="checkbox"/> 1 copy(ies) of general power attorney: reference number, if any:		
abstract : 01		4. <input type="checkbox"/> statement explaining lack of signature		
drawings : 00		5. <input type="checkbox"/> priority document(s) identified in Box No. VI as item(s):		
sequence listing part of description : 00		6. <input type="checkbox"/> translation of international application into (language):		
Total Number of Sheets: 44		7. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material		
		8. <input type="checkbox"/> nucleotide and/or amino acid sequence listing in computer readable form		
		9. <input checked="" type="checkbox"/> other (specify): postcard		
Figure of drawings which should accompany the abstract: None		Language of Filing of the international application: English		
Box No. IX SIGNATURE OF APPLICANT OR AGENT				
 T. David Reed				

For receiving Office Use only		2. Drawings <input type="checkbox"/> received: <input type="checkbox"/> not received:
1. Date of actual receipt of the purported international application	526 Rec'd PCT/PTO 19 JUL 2000	
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA/EP	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid.	

For International Bureau Use only	
Date of receipt of the record copy by the International Bureau:	
Form PCT/RO/101 (last sheet) (5 July 1998)	See Notes to the request form

GENERAL POWER OF ATTORNEY

We, **The Procter & Gamble Company**
 One Procter & Gamble Plaza
 Cincinnati, Ohio 45202
 United States of America

hereby appoint:

Reed, T. David	32,931
Hughett, Eileen L.	34,352
Sivik, Linda M.	44,982
Guffey, Timothy B.	41,048

all of 5299 Spring Grove Avenue, Cincinnati, Ohio 45217, as agents, with full power of substitution to act on our behalf before all competent international authorities in connection with any and all international applications filed by us with either The United States Patent and Trademark Office or the PCT International Bureau of WIPO as receiving office for international applications filed under the Patent Cooperation Treaty, and to make or receive payments on our behalf.

Signed in Hamilton County, State of Ohio, U.S.A., the 10th day of April 2000.

THE PROCTER & GAMBLE COMPANY




 Jacobus C. Rasser
 Assistant Secretary

STATE OF OHIO)
) ss
 COUNTY OF HAMILTON)

On this 10th day of April 2000, personally appeared before me Jacobus C. Rasser, to me personally known, who executed the foregoing instrument in my presence and acknowledged the execution thereof as his free and voluntary act and deed for the uses and purposes therein set forth and expressed.





 Virginia C. Byrd
 Notary Public, State of Ohio
 My Commission Expires October 2, 2000

CLEANING COMPOSITION

5

Technical field

The present invention is in the field of dishwashing, in particular it relates to dishwashing and automatic dishwashing products, auxiliaries and methods suitable for the removal of cooked-, baked- and burnt-on soils from cookware and tableware.

10

Background of the invention

Cooked-, baked- and burnt-on soils are amongst the most severe types of soils to remove from surfaces. Traditionally, the removal of cooked-, baked- and burnt-on soils from cookware and tableware requires soaking the soiled object prior to a mechanical action.

15 Apparently, the automatic dishwashing process alone does not provide a satisfactory removal of cooked-, baked- and burnt-on soils.

The use of cleaning compositions containing solvent for helping in the removal of cooked-, baked- and burnt-on solids is known in the art. For example, US-A-5,102,573
20 provides a method for treating hard surfaces soiled with cooked-on, baked-on or dried-on food residues comprising applying a pre-spotting composition to the soiled article. The composition applied comprises surfactant, builder, amine and solvent. WO-A-94/28108 discloses an aqueous cleaner concentrate composition, that can be diluted to form a more viscous use solution comprising an effective thickening amount of a rod micelle thickener
25 composition, lower alkyl glycol ether solvent and hardness sequestering agent. The application also describes a method of cleaning a food preparation unit having at least one substantially vertical surface having a baked food soil coating.

The use of solvents in the automatic dishwashing context is also known. JP-A-
30 10,017,900 discloses an automatic dishwashing auxiliary composition comprising non-ionic low foaming surfactant, organic solvent and water. The composition delivers detergency and drying benefits. JP-A-11,117,000 discloses a cleaning assistant

composition for automatic dishwashing machines comprising surfactant, organic high-molecular polyelectrolyte, water-soluble solvent and water. The claimed assistant composition helps in the cleaning of stubborn dirt such as that due to oil or lipstick.

- 5 There is still the need of a method and products for the removal of cooked-, baked- and burnt-on soils from cookware and tableware using an automatic dishwashing machine and avoiding the use of a pre-treatment step. There is also a need for detergent, hard-surface cleaning and dishwashing pretreatment products providing improved cleaning performance, especially on burnt-on food soils having a high carbon content.

10

Summary of the invention

- According to a first aspect of the present invention, there is provided a method of removing cooked-, baked-, or burnt-on food soil (such as grease, meat, dairy, fruit, pasta
15 and any other food especially difficult to remove after the cooking process) from cookware and tableware (including stainless steel, glass, plastic, wood and ceramic objects). The method comprises washing the cookware/tableware in an automatic dishwashing machine in the presence of an organic solvent system (comprising a single solvent compound or a mixture of solvent compounds) having a volatile organic content
20 above 1 mm Hg of less than about 50%, preferably less than about 20% and more preferably less than about 10% by weight of the solvent system. Herein volatile organic content of the solvent system is defined as the content of organic components in the solvent system having a vapor pressure higher than the prescribed limit at 25°C and atmospheric pressure.

25

- The optimum concentration of the solvent in the wash liquor is from about 100 ppm to about 10000 ppm, preferably from about 200 to about 8000 and more preferably from about 500 to about 5000 ppm. The organic solvent system is preferably used in combination with a surfactant, especially a low foaming non-ionic surfactant and a
30 detergency builder. Thus another embodiment of the invention provides a method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising washing the cookware/tableware in an automatic dishwashing machine in the

presence of surfactant, detergency builder and an organic solvent system wherein the surfactant has a wash liquor concentration of from about 10 to about 1000, preferably from about 100 to about 600 ppm, the detergency builder has a wash liquor concentration of about 100 to about 5000, preferably from about 1000 to about 3000 ppm and the
5 organic solvent system has a wash liquor concentration of from about 100 to about 10000 ppm, preferably from about 200 to about 8000 ppm and more preferably from about 500 to about 5000 ppm. The pH of the wash liquor will generally be in the alkaline range, preferably at least 10.5 or more preferably at least 11.0, this pH being provided by means of an alkalinity source or sources in one or more compositions used for delivery of the
10 solvent, surfactant and builder. Thus, according to another aspect of the invention, the removal of cooked-, baked-, or burnt-on food soil from cookware and tableware can be carried out by the use of one or more (generally unbuilt) organic solvent compositions (wherein "solvent composition" is understood to comprise the organic solvent system and optional additional active ingredients and diluents) and one or more (generally built)
15 automatic dishwashing detergent compositions. By "generally unbuilt" is meant that the composition contains less than about 5% by weight of detergency builder and "generally built" is interpreted accordingly.

According to different embodiments of the present invention, the solvent compositions
20 and automatic dishwashing detergent compositions can be delivered either at the same or at different points of the dishwashing cycle, for example: i) solvent composition and automatic dishwashing detergent composition are independently delivered in the pre-wash cycle and in the main-wash cycle, respectively; ii) a solvent composition and a first automatic dishwashing detergent composition are delivered in the pre-wash cycle and a
25 second automatic dishwashing detergent composition in the main-wash cycle; iii) a first solvent composition and a first automatic dishwashing detergent composition are delivered in the pre-wash cycle and a second solvent composition and a second automatic dishwashing detergent composition in the main-wash cycle; iv) a solvent composition and an automatic dishwashing detergent composition are delivered simultaneously in the
30 main-wash cycle; and v) a solvent composition and an automatic dishwashing detergent composition are delivered in the pre-wash and in the main-wash cycle.

Another embodiment provides a method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising washing the cookware/tableware in the pre-wash cycle of an automatic dishwashing machine in the presence of an organic solvent composition and thereafter rinsing the cookware/tableware in the rinse cycle of the automatic dishwashing machine in the presence of an automatic dishwashing rinse composition.

In preferred embodiments, the organic solvent composition and the automatic dishwashing detergent composition are delivered either i) from separate storage means (e.g. different bottles in the case of liquid compositions, different pouches, etc.) into the same cycle of an automatic dishwashing machine to provide a wash liquor concentration of organic solvent as prescribed herein and preferably in the range from about 100 to about 10000 ppm, preferably from about 500 to about 5000; or ii) from separate zones of a multi-zone storage means (e.g. multi-compartment bottle in the case of liquid compositions) into the same or different cycles of an automatic dishwashing machine. Suitably, the organic solvent composition and the automatic dishwashing detergent composition are delivered from separate zones of a multi-zone storage means at a feed ratio (solvent composition: detergent composition) in the range from about 5:1 to about 1:50, preferably from about 2:1 to about 1:5 and more preferably from about 1:1 to about 1:3 to provide a wash liquor concentration of organic solvent in the range preferably from about 100 to about 10000, more preferably from about 500 to about 5000 ppm. Alternatively, the organic solvent composition and the automatic dishwashing detergent composition are delivered from separate zones of a multi-zone storage means sequentially into the pre-wash and main wash cycle, respectively. This can be valuable in the case of product incompatibility to reduce interaction between the organic solvent composition and the automatic dishwashing detergent composition. Where, the organic solvent composition and the automatic dishwashing detergent composition are delivered simultaneously from separate zones of a multi-zone storage means, the physical form of the organic solvent composition and/or automatic dishwashing detergent composition is preferably such as to prevent intimate mixing of the compositions prior to contact thereof with the wash liquor.

The invention can be also reduced to practice using multi-phase, "all-in-one" products. Thus, according to another embodiment of the invention, there is provided a method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising delivering separate portions of a multi-phase detergent composition into the same or different cycles of an automatic dishwashing machine, wherein the multi-phase detergent composition comprises at least a first phase containing an organic solvent composition and at least a second phase containing an automatic dishwashing detergent composition. The multiphase detergent composition, for example could take the form of a multi-layer liquid (e.g. coacervate) or gel contained in a bottle, or a multiphase tablet incorporating the solvent composition in the form of a gel contained within a preformed cavity or recess within the main tablet body. In either instance, the level of solvent delivered to the wash process should be such as to deliver the benefits on cooked-, baked- or burnt-on food soils.

The present invention also envisages the use of multiple organic solvent compositions. Thus according to a further aspect of the invention, there is provided a method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising delivering a plurality of organic solvent compositions of different solvent characteristics into the same or different cycles of an automatic dishwashing machine, for example, a first solvent composition in the pre-wash cycle and a second solvent composition in the main-wash cycle. For optimum performance, the different organic solvent compositions are designed to be specific to different soil and/or substrates. They can be delivered into different cycles of a dishwashing machine, with or without different automatic dishwashing detergent compositions, such that, for example, a first solvent composition and a first automatic dishwashing detergent composition are delivered into the pre-wash cycle and a second solvent composition and a second automatic dishwashing detergent composition are delivered into the main-wash cycle.

In another embodiment of the invention the organic solvent composition can be in a unit dose form allowing controlled release (for example delayed, sustained, triggered or slow release) of the composition during one or more repeated washing cycles. In preferred

unit dose forms, the solvent composition is contained in a single or multi-compartment pouch.

The invention can also be applied to single-phase "all-in-one" products. According to this aspect, a method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprises washing the cookware/tableware in an automatic dishwashing machine with an automatic dishwashing detergent composition comprising surfactant (preferably comprising low-foaming nonionic surfactant), detergency builder and organic solvent system in levels sufficient to provide a wash liquor concentration of from about 10 ppm to about 1000 ppm surfactant, from about 100 ppm to about 5000 ppm detergency builder, and about 100 ppm to about 10,000, preferably from about 500 ppm to about 5000 ppm of organic solvent.

In the methods of the invention the organic solvent composition can be in the form of a liquid, paste, cream or gel and can be optionally encapsulated, packaged in a single- or multi-compartment pouch, or absorbed onto a porous carrier material. The solvent composition can be aqueous but preferably is anhydrous. Preferred pouches for use herein are water-soluble, solvent-resistant partially hydrolysed PVA pouches.

The optimum organic solvent systems for use herein are characterised by extremely low liquid surface tensions and contact angles on polymerised grease-coated substrates. Moreover, they generally consist of mixed solvent systems displaying synergistic contact angle and low surface tension. The organic solvent system herein preferably has a liquid surface tension at 25°C of less than about 27 mN/m. In terms of contact angle, compositions containing the solvent system preferably display an advancing contact angle on a polymerised grease-coated substrate at 25°C of less than 20°, preferably less than 10° and more preferably less than 5°. Furthermore, the advancing contact angle for compositions based on mixed solvent systems should be less than that of any of the corresponding compositions containing the individual components of the solvent system. Such solvent systems and compositions are found to be optimum for the removal of burnt-on soils having a high carbon content from cookware and tableware.

It is a feature of the invention that these solvent systems also display excellent performance in dried application to soiled cookware and tableware. Thus, according to another aspect of the invention, there is provided a method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising treating the cookware/tableware with a hard surface cleaning composition comprising an organic solvent system. The organic solvent system desirably has a liquid surface tension of less than about 27 mN/m, preferably less than about 26 mN/m. The hard surface cleaning composition on the other hand desirably display an advancing contact angle on a polymerised grease-coated substrate at 25°C of less than 20°, preferably less than 10° and more preferably less than 5°. Preferably, the above method comprises the step of pre-treating the cookware/tableware with the hard surface cleaning composition prior to manual or automatic dishwashing.

A broad range of organic solvents are suitable for use herein but preferably the organic solvent is selected from alcohols, amines, esters, glycol ethers, glycols, terpenes and mixtures thereof. The organic solvent system is preferably formulated to meet the constraints on volatile solvent components described above and in highly preferred embodiments the solvent system will contain less than about 50%, preferably less than 20% and more preferably less than 10% of solvent components having a vapor pressure above about 0.1 mm Hg at 25°C and atmospheric pressure. In highly preferred embodiments, the solvent is essentially free (contains less than about 5% by weight) of solvent components having a boiling point below about 150°C, flash point below about 100°C or a vapor pressure above about 1 mm Hg at 25°C and atmospheric pressure.

The organic solvent system is preferably selected from organoamine solvents, inclusive of alkanolamines, alkylamines, alkyleneamines and mixtures thereof; alcoholic solvents inclusive of aromatic, aliphatic (preferably C₄-C₁₀) and cycloaliphatic alcohols and mixtures thereof; glycols and glycol derivatives inclusive of C₂-C₃ (poly)alkylene glycols, glycol ethers, glycol esters and mixtures thereof; and mixtures selected from organoamine solvents, alcoholic solvents, glycols and glycol derivatives. In one preferred embodiment the organic solvent comprises organoamine (especially alkanolamine) solvent and glycol ether solvent, preferably in a weight ratio of from about 3:1 to about

1:3, and wherein the glycol ether solvent is selected from ethylene glycol monobutyl ether, diethylene glycol monobutyl ether, ethylene glycol monomethyl ether, ethylene glycol monoethyl ether, diethylene glycol monomethyl ether, diethylene glycol monoethyl ether, propylene glycol monobutyl ether, and mixtures thereof. Preferably, the glycol ether is a mixture of diethylene glycol monobutyl ether and propylene glycol butyl ether, especially in a weight ratio of from about 1:2 to about 2:1. In other preferred embodiments, suitable organic solvents include one or more water-soluble or dispersible, preferably hydroxylated organoamine solvents, especially alkanolamine solvents having a pKa of at least 8.8, preferably at least 9.3 and more preferably at least 9.8. In these embodiments, the organic solvent system preferably comprises a mixture of a first organoamine solvent having a pKa of about 9.5 or less and a second organoamine solvent having a pKa greater than about 9.5. Also preferred for use herein are organic solvents comprising salts of organoamines which are introduced into the wash liquor of the automatic dishwashing machine at a wash liquor pH above the highest pKa of the organoamine and which thereby act as a source of organoamine solvent. Suitable salt counterions include halides such as chloride and bromide, oxyanions such as sulphate, borate, phosphate, pyrophosphate and polyphosphate and surfactant anions.

The effect of the solvent system can be further improved by the addition of certain wetting agents. Preferably, the organic solvent system is used in conjunction with a wetting agent effective in lowering the surface tension of the solvent system, preferably to at least 1 mN/m less than that of the wetting agent, the wetting agent preferably being selected from organic surfactants having a surface tension less than about 30 mN/m, more preferably less than about 28 mN/m and specially less than about 26 mN/m. Preferred wetting agents for use herein are silicone polyether copolymers, especially silicone poly(alkyleneoxide) copolymers wherein alkylene is selected from ethylene, propylene and mixtures thereof.

In terms of solvent parameters, the organic solvent can be selected from:

- a) polar, hydrogen-bonding solvents having a Hansen solubility parameter of at least 20 (Mpa)^{1/2}, a polarity parameter of at least 7 (Mpa)^{1/2}, preferably at least 12 (Mpa)^{1/2} and a hydrogen bonding parameter of at least 10 (Mpa)^{1/2}

- b) polar non-hydrogen bonding solvents having a Hansen solubility parameter of at least $20 \text{ (Mpa)}^{1/2}$, a polarity parameter of at least $7 \text{ (Mpa)}^{1/2}$, preferably at least $12 \text{ (Mpa)}^{1/2}$ and a hydrogen bonding parameter of less than $10 \text{ (Mpa)}^{1/2}$
- c) amphiphilic solvents having a Hansen solubility parameter below $20 \text{ (Mpa)}^{1/2}$, a polarity parameter of at least $7 \text{ (Mpa)}^{1/2}$ and a hydrogen bonding parameter of at least $10 \text{ (Mpa)}^{1/2}$
- d) non-polar solvents having a polarity parameter below $7 \text{ (Mpa)}^{1/2}$ and a hydrogen bonding parameter below $10 \text{ (Mpa)}^{1/2}$ and
- e) mixtures thereof.

10

The invention also relates to detergent packs and multi-component products suitable for use in an automatic dishwashing machine or dishwashing pretreatment to provide baked and burnt-on soil removal and other cleaning benefits. In one embodiment, there is provided an automatic dishwashing detergent pack comprising two or more automatic dishwashing detergent and/or auxiliary products, storage means comprising separate but associated portions of the two or more products and means, for example electric pump means, for delivering quantities of the two or more products into the same or different cycles of an automatic dishwashing machine. The pack can also comprise means for controlling the relative dispensing rate of the two or more products from the storage means. The pack preferably comprises an organic solvent composition and an automatic dishwashing detergent composition and is used for removing cooked-, baked-, and burnt-on food soil from cookware and tableware. In a preferred embodiment the two or more automatic dishwashing detergent or auxiliary products are in rheology-matched gel-form. Compositions are considered to be rheology-matched if they have similar yield values (differing by less than about 50%, preferably by less than about 20%) and/or similar viscosities (differing by less than about 50%, preferably by less than about 20%) under the same shear conditions.

The invention also relates to organic solvent compositions suitable for use in automatic dishwashing or dishwashing pretreatment. In one embodiment, an organic solvent composition comprises about 1% to about 99%, preferably from about 5% to about 90% of an organic solvent system for removing cooked-, baked-, or burnt-on food soil from

30

cookware and tableware, from about 0.5% to about 50%, preferably from about 5% to about 25% of bleach and from about 0.0001% to about 10% of detergency enzyme. The compositions preferably are in gel-form and contain a thickener such as methylcellulose or other nonionic cellulosic thickener. The solvent compositions are preferably
5 anhydrous (containing less than about 5%, preferably less than about 1% of water) and comprise bleach in the form of a particulate suspension having an average particle size in the range from about 10 to about 100 μ m, preferably from about 25 to about 75 μ m. The compositions are also builder free or generally builder free. It is a feature of the invention that a broad range of solvents, including organoamine solvents can be
10 incorporated in the solvent compositions of the invention with acceptable bleach stability provided the water content of the composition is carefully controlled.

The invention also relates to detergent compositions suitable for use in automatic dishwashing or dishwashing pretreatment. In one embodiment, an automatic dishwashing
15 detergent composition comprises from about 0.05% to about 10% by weight of a low-foaming non-ionic surfactant, from about 1% to about 30% of an organoamine, preferably alkanolamine (especially monoethanolamine) solvent and at least about 5% by weight of a detergency builder. Preferably, the automatic dishwashing detergent composition is in the form of a gel comprising from about 2% to about 20%, preferably from 5% to 15% by
20 weight of an alkanolamine, at least about 5% by weight of detergency builder, and from about 0.1% to about 5% by weight of a low foaming non-ionic surfactant. Although any non-ionic low foaming surfactant (or combination of non-ionic surfactants and suds suppressers) can be used herein, capped nonionic surfactants and combinations or amine oxide and capped non-ionic surfactants are preferred. The compositions also preferably
25 have a pH (1% aqueous solution) in excess of about 9.0, preferably in excess of about 10.5 and more preferably greater than about 11.

In one embodiment, an automatic dishwashing detergent composition comprises from about 0.05% to about 10% by weight of a low-foaming non-ionic surfactant, from about
30 1% to about 30% of an organic solvent, preferably alkanolamine solvent, at least about 5% by weight of a detergency builder and a wetting agent, preferably a silicone-poly(alkyleneoxide) copolymers.

- In a preferred embodiment an automatic dishwashing detergent pack is provided, comprising: i) an organic solvent composition suitable for use in automatic dishwashing comprising from about 1% to about 99%, preferably from about 5% to about 90%,
5 especially from about 40% to about 80% of an organic solvent system for removing cooked-, baked-, or burnt-on food soil from cookware and tableware, from about 0.5% to about 50%, preferably from about 5% to about 25% of bleach, from about 0.0001% to about 10% of detergency enzyme, and wherein the composition is in the form of an anhydrous gel comprising bleach in the form of a particulate suspension; and ii) an
10 automatic dishwashing detergent composition comprising from about 0.05% to about 10% by weight of a low-foaming non-ionic surfactant, optionally from about 1% to about 30% of an organoamine, preferably alkanolamine solvent, and at least about 5% by weight of a detergency builder. Preferably, the automatic dishwashing detergent composition is in the form of a gel comprising from about 2% to about 20%, preferably
15 from about 5% to about 15% by weight of the composition of an alkanolamine, at least about 5% by weight of detergency builder (such as sodium potassium tripolyphosphate), and from about 0.1% to about 5% by weight of the composition of a low foaming non-ionic surfactant.
- 20 The invention also relates to hard-surface cleaning and dishwashing pretreatment compositions comprising the herein defined solvent systems for direct application to burnt-on and baked-on food soiled cookware and tableware. Preferred are compositions comprising an organic solvent system having a liquid surface tension of less than about 27 mN/m. Also preferred are compositions in the form of a liquid or gel and having a pH
25 of greater than about 10.5, preferably greater than about 11. Preferred compositions contain from about 1% to about 99% preferably from about 5% to about 50% of organic solvent as herein defined, highly preferred being a mixed solvent system based on alkanolamine and a mixed glycol ether solvent system as described hereinabove.
- 30 The present invention also provides a hard-surface cleaning or dishwashing pretreatment composition for removing cooked-, baked-, or burnt-on food soil from cookware and tableware, the composition comprising an organic solvent system having an advancing

contact angle on a polymerised grease-coated substrate of less than 20°, preferably less than 10° and more preferably less than 5°. Preferably, the hard-surface cleaning composition comprises an organic solvent system comprising a plurality of solvent components in levels such that the composition has an advancing contact angle on
5 polymerised grease of less than that of any of the corresponding compositions containing the individual components of the solvent system.

The method for determining contact angle is as follows. A sample plate (prepared as described below) is dipped into and pulled out of a liquid and contact angles calculated
10 after Wilhelmy Method. The force exerted on the sample according to the immersion depth is measured (using a Kruss K12 tensiometer and System K121 software) and is proportional to the contact angle of the liquid on the solid surface. The sample plate is prepared as follows: Spray 30-50 grams of Canola Oil into a beaker. Dip a glass slide (3x9x0.1 cm) into the Oil and thoroughly coat the surface. This results in an evenly
15 dispersed layer of oil on the surface. Adjust the weight of product on the slide's surface until approximately 0.5 g of oil has been delivered and evenly distributed. At this point, bake the slides at 450F for 20 minutes, and allow to cool to room temperature.

The compositions of the invention are also characterised by having a low volatile organic
20 content, preferably with a volatile organic content less than about 20%, preferably less than about 10% and more preferably less than about 5%.

Apart from the solvent parameters described above, the compositions of the invention designed for hard surface cleaning or dishwashing pretreatment use should also meet
25 certain rheological and other performance parameter including both the ability to be sprayed and the ability to cling to surfaces. For example, it is desirable that the product sprayed on a vertical stainless steel surface has a flow velocity less than about 1 cm/sec, preferably less than about 0.1 cm/s. For this purpose, the product is in the form of a shear thinning fluid having a shear index from about 0.3 to about 0.7, preferably from about 0.4
30 to about 0.6 and a consistency index from about 0.20 to about 0.15, preferably from about 0.175 to about 0.160 kg/(m s²⁻ⁿ). The product preferably has a viscosity from about 0.1 to about 200 Pa s, preferably from about 0.3 to about 20 Pa s as measured with a Brookfield

cylinder viscometer (model LVDII) using 10 ml sample, a spindle S-31 and a speed of 3 rpm.

5 It is a feature of the invention that many of the solvent systems and compositions of the invention that are optimum for cleaning also demonstrate improved compatibility with partially hydrolysed PVA pouch materials of known construction and type. This is particularly surprising given that many well-known polar/or hydrolysed bonding solvent materials (for example the organoamines) in themselves have low compatibility with PVA materials and present serious issues for product stability. Solvent systems
10 comprising mixtures of polar hydrogen bonding solvents (such as the organoamines) with a cosolvent selected from polar non-hydrogen bonding, amphiphilic and non-polar solvents and mixtures thereof are particularly valuable in this respect. Also valuable for improved PVA compatibility are organoamines present in composition in the form of amine salt. Compositions suitable for inclusion in pouches will normally comprise a
15 major proportion of solvent system components, preferably at least 50% by weight, more preferably at least 70% by weight or even higher.

Finally, there is also disclosed the use of an organic solvent system in an automatic dishwashing machine to remove cooked-, baked-, or burnt-on food soil from cookware
20 and tableware.

Detailed description of the invention

The present invention envisages the use of solvent compositions as additives for
25 conventional automatic dishwashing detergent compositions. It also envisages multi-component dishwashing products containing purpose-designated combination of solvent compositions and dishwashing detergent compositions. The invention also envisages so called "all-in-one" detergent and hard surface cleaning products having both an alkaline detergent and a solvent functionality. In the case of additive and multi-component
30 products, the invention does not require the two compositions to be in the same physical form. The organic solvent composition can be in any physical form, e.g. liquid, paste, cream, gel, powder, granules or tablets and similarly the automatic dishwashing detergent

composition can be in any of these forms. Preferably, however, both compositions are in the form of liquids or gels or the organic solvent composition is in the form of liquid or gel and the automatic dishwashing detergent composition is in the form of powder, granules or tablet. The compositions used herein can be dispensed from any suitable
5 device, such as bottles (pump assisted bottles, squeeze bottles), paste dispensers, capsules, multi-compartment bottles, multi-compartment capsules, pouches, and multi-compartment pouches, etc.

The solvent compositions herein comprise one or more organic solvents and can
10 additionally comprises surfactant, bleach, enzyme, enzyme stabilising components, thickener, etc.

The organic solvents should be selected so as to be compatible with the tableware/cookware as well as with the different parts of an automatic dishwashing
15 machine. Furthermore, the solvent system should be effective and safe to use having a volatile organic content above 1 mm Hg (and preferably above 0.1 mm Hg) of less than about 50%, preferably less than about 30%, more preferably less than about 10% by weight of the solvent system. Also they should have very mild pleasant odours. The individual organic solvents used herein generally have a boiling point above about 150°C,
20 flash point above about 100°C and vapor pressure below about 1 mm Hg, preferably below 0.1 mm Hg at 25°C and atmospheric pressure.

Solvents that can be used herein include: i) alcohols, such as benzyl alcohol, 1,4-cyclohexanedimethanol, 2-ethyl-1-hexanol, furfuryl alcohol, 1,2-hexanediol and other
25 similar materials; ii) amines, such as alkanolamines (e.g. primary alkanolamines: monoethanolamine, monoisopropanolamine, diethylethanolamine, ethyl diethanolamine; secondary alkanolamines: diethanolamine, diisopropanolamine, 2-(methylamino)ethanol; ternary alkanolamines: triethanolamine, triisopropanolamine); alkylamines (e.g. primary alkylamines: monomethylamine, monoethylamine, monopropylamine, monobutylamine,
30 monopentylamine, cyclohexylamine), secondary alkylamines: (dimethylamine), alkylene amines (primary alkylene amines: ethylenediamine, propylenediamine) and other similar materials; iii) esters, such as ethyl lactate, methyl ester, ethyl acetoacetate, ethylene

glycol monobutyl ether acetate, diethylene glycol monoethyl ether acetate, diethylene glycol monobutyl ether acetate and other similar materials; iv) glycol ethers, such as ethylene glycol monobutyl ether, diethylene glycol monobutyl ether, ethylene glycol monomethyl ether, ethylene glycol monoethyl ether, diethylene glycol monomethyl ether, 5 diethylene glycol monoethyl ether, propylene glycol butyl ether and other similar materials; v) glycols, such as propylene glycol, diethylene glycol, hexylene glycol (2-methyl-2, 4 pentanediol), triethylene glycol, composition and dipropylene glycol and other similar materials; and mixtures thereof.

- 10 Preferred solvent systems to be used herein are systems comprising alkanolamines, especially monoethanolamine and combinations of monoethanolamine and 2-(methylamino)ethanol.

The detergent and cleaning compositions herein can comprise traditional detergency 15 components and can also comprise organic solvents having a cleaning function and organic solvents having a carrier or diluent function or some other specialised function. The compositions will generally be built and comprise one or more detergent active components which may be selected from colorants, bleaching agents, surfactants, alkalinity sources, enzymes, thickeners (in the case of liquid, paste, cream or gel 20 compositions) and disrupting and binding agents (in the case of powder, granules or tablets). Highly preferred detergent components include a builder compound, an alkalinity source, a surfactant, an enzyme and a bleaching agent.

Unless otherwise specified, the components described hereinbelow can be incorporated either in the organic solvent compositions and/or the detergent or cleaning compositions.

25

Surfactant

In compositions and methods of the present invention for use in automatic dishwashing the detergent surfactant is preferably low foaming by itself or in combination with other components (i.e. suds suppressers). In compositions and methods of the present 30 invention for use in hard surface cleaning or pretreatment prior to dishwashing, the detergent surfactant is preferably foamable in direct application but low foaming in automatic dishwashing use. Surfactants suitable herein include anionic surfactants such

as alkyl sulfates, alkyl ether sulfates, alkyl benzene sulfonates, alkyl glyceryl sulfonates, alkyl and alkenyl sulphonates, alkyl ethoxy carboxylates, N-acyl sarcosinates, N-acyl taurates and alkyl succinates and sulfosuccinates, wherein the alkyl, alkenyl or acyl moiety is C₅-C₂₀, preferably C₁₀-C₁₈ linear or branched; cationic surfactants such as chlorine esters (US-A-4228042, US-A-4239660 and US-A-4260529) and mono C₆-C₁₆ N-alkyl or alkenyl ammonium surfactants wherein the remaining N positions are substituted by methyl, hydroxyethyl or hydroxypropyl groups; low and high cloud point nonionic surfactants and mixtures thereof including nonionic alkoxyated surfactants (especially ethoxylates derived from C₆-C₁₈ primary alcohols), ethoxylated-propoxylated alcohols (e.g., Olin Corporation's Poly-Tergent® SLF18), epoxy-capped poly(oxyalkylated) alcohols (e.g., Olin Corporation's Poly-Tergent® SLF18B - see WO-A-94/22800), ether-capped poly(oxyalkylated) alcohol surfactants, and block polyoxyethylene-polyoxypropylene polymeric compounds such as PLURONIC®, REVERSED PLURONIC®, and TETRONIC® by the BASF-Wyandotte Corp., Wyandotte, Michigan; amphoteric surfactants such as the C₁₂-C₂₀ alkyl amine oxides (preferred amine oxides for use herein include lauryldimethyl amine oxide and hexadecyl dimethyl amine oxide), and alkyl amphocarboxylic surfactants such as Miranol™ C2M; and zwitterionic surfactants such as the betaines and sultaines; and mixtures thereof. Surfactants suitable herein are disclosed, for example, in US-A-3,929,678, US-A-4,259,217, EP-A-0414 549, WO-A-93/08876 and WO-A-93/08874. Surfactants are typically present at a level of from about 0.2% to about 30% by weight, more preferably from about 0.5% to about 10% by weight, most preferably from about 1% to about 5% by weight of composition. Preferred surfactant for use herein are low foaming and include low cloud point nonionic surfactants and mixtures of higher foaming surfactants with low cloud point nonionic surfactants which act as suds suppresser therefor.

Builder

Builders suitable for use in detergent and cleaning compositions herein include water-soluble builders such as citrates, carbonates and polyphosphates e.g. sodium tripolyphosphate and sodium tripolyphosphate hexahydrate, potassium tripolyphosphate and mixed sodium and potassium tripolyphosphate salts; and partially water-soluble or

insoluble builders such as crystalline layered silicates (EP-A-0164514 and EP-A-0293640) and aluminosilicates inclusive of Zeolites A, B, P, X, HS and MAP. The builder is typically present at a level of from about 1% to about 80% by weight, preferably from about 10% to about 70% by weight, most preferably from about 20% to about 60% by weight of composition.

Amorphous sodium silicates having an $\text{SiO}_2:\text{Na}_2\text{O}$ ratio of from 1.8 to 3.0, preferably from 1.8 to 2.4, most preferably 2.0 can also be used herein although highly preferred from the viewpoint of long term storage stability are compositions containing less than about 22%, preferably less than about 15% total (amorphous and crystalline) silicate.

Enzyme

Enzymes suitable herein include bacterial and fungal cellulases such as Carezyme and Celluzyme (Novo Nordisk A/S); peroxidases; lipases such as Amano-P (Amano Pharmaceutical Co.), M1 Lipase^R and Lipomax^R (Gist-Brocades) and Lipolase^R and Lipolase Ultra^R (Novo); cutinases; proteases such as Esperase^R, Alcalase^R, Durazym^R and Savinase^R (Novo) and Maxatase^R, Maxacal^R, Properase^R and Maxapem^R (Gist-Brocades); and α and β amylases such as Purafect Ox Am^R (Genencor) and Termamyl^R, Ban^R, Fungamyl^R, Duramyl^R, and Natalase^R (Novo); and mixtures thereof. Enzymes are preferably added herein as prills, granulates, or cogramulates at levels typically in the range from about 0.0001% to about 2% pure enzyme by weight of composition.

Bleaching agent

Bleaching agents suitable herein include chlorine and oxygen bleaches, especially inorganic perhydrate salts such as sodium perborate mono-and tetrahydrates and sodium percarbonate optionally coated to provide controlled rate of release (see, for example, GB-A-1466799 on sulfate/carbonate coatings), preformed organic peroxyacids and mixtures thereof with organic peroxyacid bleach precursors and/or transition metal-containing bleach catalysts (especially manganese or cobalt). Inorganic perhydrate salts are typically incorporated at levels in the range from about 1% to about 40% by weight,


preferably from about 2% to about 30% by weight and more preferably from about 5% to about 25% by weight of composition. Peroxyacid bleach precursors preferred for use herein include precursors of perbenzoic acid and substituted perbenzoic acid; cationic peroxyacid precursors; peracetic acid precursors such as TAED, sodium acetoxybenzene sulfonate and pentaacetylglucose; pernonanoic acid precursors such as sodium 3,5,5-trimethylhexanoyloxybenzene sulfonate (iso-NOBS) and sodium nonanoyloxybenzene sulfonate (NOBS); amide substituted alkyl peroxyacid precursors (EP-A-0170386); and benzoxazin peroxyacid precursors (EP-A-0332294 and EP-A-0482807). Bleach precursors are typically incorporated at levels in the range from about 0.5% to about 25%, preferably from about 1% to about 10% by weight of composition while the preformed organic peroxyacids themselves are typically incorporated at levels in the range from 0.5% to 25% by weight, more preferably from 1% to 10% by weight of composition. Bleach catalysts preferred for use herein include the manganese triazacyclononane and related complexes (US-A-4246612, US-A-5227084); Co, Cu, Mn and Fe bispyridylamine and related complexes (US-A-5114611); and pentamine acetate cobalt(III) and related complexes(US-A-4810410).

Low cloud point non-ionic surfactants and suds suppressers

The suds suppressers suitable for use herein include nonionic surfactants having a low cloud point. "Cloud point", as used herein, is a well known property of nonionic surfactants which is the result of the surfactant becoming less soluble with increasing temperature, the temperature at which the appearance of a second phase is observable is referred to as the "cloud point" (See Kirk Othmer, pp. 360-362). As used herein, a "low cloud point" nonionic surfactant is defined as a nonionic surfactant system ingredient having a cloud point of less than 30° C., preferably less than about 20° C., and even more preferably less than about 10° C., and most preferably less than about 7.5° C. Typical low cloud point nonionic surfactants include nonionic alkoxyated surfactants, especially ethoxylates derived from primary alcohol, and polyoxypropylene/polyoxyethylene/polyoxypropylene (PO/EO/PO) reverse block polymers. Also, such low cloud point nonionic surfactants include, for example, ethoxylated-propoxylated alcohol (e.g., Olin Corporation's Poly-Tergent® SLF18) and

epoxy-capped poly(oxyalkylated) alcohols (e.g., Olin Corporation's Poly-Tergent® SLF18B series of nonionics, as described, for example, in US-A-5,576,281).

Preferred low cloud point surfactants are the ether-capped poly(oxyalkylated) suds suppresser having the formula:



wherein R^1 is a linear, alkyl hydrocarbon having an average of from about 7 to about 12 carbon atoms, R^2 is a linear, alkyl hydrocarbon of about 1 to about 4 carbon atoms, R^3 is a linear, alkyl hydrocarbon of about 1 to about 4 carbon atoms, x is an integer of about 1 to about 6, y is an integer of about 4 to about 15, and z is an integer of about 4 to about 25.

Other low cloud point nonionic surfactants are the ether-capped poly(oxyalkylated) having the formula:



wherein, R_I is selected from the group consisting of linear or branched, saturated or unsaturated, substituted or unsubstituted, aliphatic or aromatic hydrocarbon radicals having from about 7 to about 12 carbon atoms; R_{II} may be the same or different, and is independently selected from the group consisting of branched or linear C_2 to C_7 alkylene in any given molecule; n is a number from 1 to about 30; and R_{III} is selected from the group consisting of:

- (i) a 4 to 8 membered substituted, or unsubstituted heterocyclic ring containing from 1 to 3 hetero atoms; and
 - (ii) linear or branched, saturated or unsaturated, substituted or unsubstituted, cyclic or acyclic, aliphatic or aromatic hydrocarbon radicals having from about 1 to about 30 carbon atoms;
- (b) provided that when R^2 is (ii) then either: (A) at least one of R^1 is other than C_2 to C_3 alkylene; or (B) R^2 has from 6 to 30 carbon atoms, and with the further

proviso that when R^2 has from 8 to 18 carbon atoms, R is other than C_1 to C_5 alkyl.

Other suitable components herein include organic polymers having dispersant, anti-
5 redeposition, soil release or other detergency properties in levels of from about 0.1% to about 30%, preferably from about 0.5% to about 15%, most preferably from about 1% to about 10% by weight of composition. Preferred anti-redeposition polymers herein include acrylic acid containing polymers such as Sokalan PA30, PA20, PA15, PA10 and Sokalan CP10 (BASF GmbH), Acusol 45N, 480N, 460N (Rohm and Haas),
10 acrylic acid/maleic acid copolymers such as Sokalan CP5 and acrylic/methacrylic copolymers. Preferred soil release polymers herein include alkyl and hydroxyalkyl celluloses (US-A-4,000,093), polyoxyethylenes, polyoxypropylenes and copolymers thereof, and nonionic and anionic polymers based on terephthalate esters of ethylene glycol, propylene glycol and mixtures thereof.

15 Heavy metal sequestrants and crystal growth inhibitors are suitable for use herein in levels generally from about 0.005% to about 20%, preferably from about 0.1% to about 10%, more preferably from about 0.25% to about 7.5% and most preferably from about 0.5% to about 5% by weight of composition, for example diethylenetriamine penta
20 (methylene phosphonate), ethylenediamine tetra(methylene phosphonate) hexamethylenediamine tetra(methylene phosphonate), ethylene diphosphonate, hydroxyethylene-1,1-diphosphonate, nitrilotriacetate, ethylenediaminetetracetate, ethylenediamine- N,N' -disuccinate in their salt and free acid forms.

25 The compositions herein can contain a corrosion inhibitor such as organic silver coating agents in levels of from about 0.05% to about 10%, preferably from about 0.1% to about 5% by weight of composition (especially paraffins such as Winog 70 sold by Wintershall, Salzbergen, Germany), nitrogen-containing corrosion inhibitor compounds (for example benzotriazole and benzimidazole - see GB-A-1137741) and Mn(II) compounds,
30 particularly Mn(II) salts of organic ligands in levels of from about 0.005% to about 5%, preferably from about 0.01% to about 1%, more preferably from about 0.02% to about 0.4% by weight of the composition.

Other suitable components herein include colorants, water-soluble bismuth compounds such as bismuth acetate and bismuth citrate at levels of from about 0.01% to about 5%, enzyme stabilizers such as calcium ion, boric acid, propylene glycol and chlorine bleach scavengers at levels of from about 0.01% to about 6%, lime soap dispersants (see WO-A-93/08877), suds suppressors (see WO-93/08876 and EP-A-0705324), polymeric dye transfer inhibiting agents, optical brighteners, perfumes, fillers and clay.

Liquid detergent compositions can contain water and other volatile solvents as carriers. Low quantities of low molecular weight primary or secondary alcohols such as methanol, ethanol, propanol and isopropanol can be used in the liquid detergent of the present invention. Other suitable carrier solvents used in low quantities includes glycerol, propylene glycol, ethylene glycol, 1,2-propanediol, sorbitol and mixtures thereof.

15

Examples

Abbreviations used in Examples

In the examples, the abbreviated component identifications have the following meanings:

Carbonate	:	Anhydrous sodium carbonate
STPP	:	Sodium tripolyphosphate
SKTP	:	Sodium potassium tripolyphosphate
Silicate 3.2	:	Amorphous Sodium Silicate ($\text{SiO}_2\text{:Na}_2\text{O}$ ratio = 3:2)
Silicate	:	Amorphous Sodium Silicate ($\text{SiO}_2\text{:Na}_2\text{O}$ ratio = 2.0)
SKS-6	:	Crystalline layered silicate of formula $\delta\text{-Na}_2\text{Si}_2\text{O}_5$
KOH	:	Potassium hydroxide
H ₂ SO ₄	:	Sulphuric acid
HEDP	:	Ethane 1-hydroxy-1,1-diphosphonic acid

PB1	:	Sodium perborate monohydrate average particle size 770 μm
PB1-50	:	Sodium perborate monohydrate average particle size 50 μm
Termamyl	:	α -amylase available from Novo Nordisk A/S
FN3	:	protease available from Genencor
Savinase	:	protease available from Novo Nordisk A/S
LF404	:	low foaming surfactant available from Olin Corporation
SLF18	:	low foaming surfactant available from Olin Corporation
ACNI	:	alkyl capped non-ionic surfactant of formula $\text{C}_{9/11} \text{H}_{19/23}$ EO_8 -cyclohexyl acetal
C_{16}AO	:	hexadecyl dimethyl amine oxide
PA30	:	Polyacrylate homo-polymer of molecular weight approximately 8,000 available from BASF
Proxel GXL	:	preservative(1,2-benzisothiazolin-3-one) available from Zeneca, Inc
Polygel premix	:	5% active Polygel DKP in water available from 3V Inc.
CaCl_2	:	Calcium chlorine
CHDM	:	Cyclohexane dimethanol
BTA	:	Benzotriazole
Winog	:	Paraffin oil sold by Wintershall.
Vivapur	:	Microcrystalline cellulose of average particle size 0.18 mm
Triacetate	:	Sodium acetate trihydrate
Duramyl	:	α -amylase available from Novo Nordisk A/S
Sulphate	:	Anhydrous sodium sulphate.
Citric Acid	:	Anhydrous Citric acid
Bicarbonate	:	Sodium hydrogen carbonate
PEG 400	:	Polyethylene Glycol molecular weight approximately 400 available from Hoechst

PEG 4000	:	Polyethylene Glycol molecular weight approximately 4000 available from Hoechst
PVPVI	:	Polyvinylpyrrolidone vinylimidazole copolymer molecular weight approximately 15,000 available from BASF
MEA	:	Monoethanolamine
MAE	:	2-(methylamino)ethanol
SF1488	:	Polydimethylsiloxane copolymer
Dowanol PNB	:	Propylene glycol butyl ether

In the following examples all levels are quoted as parts by weight.

Examples 1 to 5

- 5 A combination of solvent compositions and automatic dishwashing detergents are used to wash a load of tableware and cookware having cooked-on, baked-on and burnt-on food soils. The load comprises different soils and different substrates: lasagne baked for 2 hours at 140°C on Pyrex, lasagne cooked for 2 hours at 150°C on stainless steel, potato and cheese cooked for 2 hours at 150°C on stainless steel, egg yolk cooked for 2 hours at
- 10 150°C on stainless steel and sausage cooked for 1 hour at 120°C followed by 1 hour at 180°C. The load is washed in a 5 litre liquor capacity Bosch 6032 dishwashing machine, at 55°C without prewash, using the compositions given in Examples 1 to 5. Examples 1 to 5 illustrate the use of a combination of a two-phase automatic dishwashing detergent tablet and an organic solvent composition added separately to the main-wash cycle of the
- 15 dishwashing machine. The two-component compositions of examples 1 to 5 provided excellent removal of cooked-on, baked-on and burnt-on food soils.

Example	1	2	3	4	5
<u>Dishwashing detergent composition</u>					
<u>Phase 1</u>					
Carbonate	3.5	3.4	5.030	3.375	5.063

STPP	10.1	10.1	9.49	9.85	8.73
Silicate	1.1	1.0	1.58	1.61	1.548
SKS-6	1.5	1.4	2.16	1.425	2.138
HEDP	0.18	0.18	0.27	0.18	0.27
PB1	2.45	2.45	3.53	2.4	3.6
Termamyl	0.11	0.11	0.16	0.11	0.165
FN3			0.15		
Savinase	0.12	0.12	0.17	0.12	0.18
LF404	0.60	0.60	0.86		
SLF18				0.60	0.90
C ₁₆ AO				0.16	0.24
PA30		0.1		0.1	0.15
CHDM				0.02	0.03
BTA	0.06	0.03	0.09	0.045	0.068
PEG 4000	0.26	0.26	0.44		
Winog	0.1	0.07	0.09	0.065	0.098
Vivapur			0.48	0.32	0.48
Triacetate			0.72		
Perfume	0.02	0.02	0.01		
<u>Total</u>	20.1g	19.84g	25.23g	21.05g	24.663g
<u>Phase 2</u>					
FN3	0.29	0.499	0.29	0.499	0.499
Termamyl	0.29	0.29	0.29	0.29	0.29
Citric acid	0.23	0.1	0.23	0.1	0.1
Bicarbonate	0.62	0.289	0.62	0.289	0.289
PEG 400	0.02	0.01	0.02	0.01	0.01
PEG 4000	0.07	0.2	0.07	0.2	0.2
PVPVI		0.095		0.095	0.095
Potassium Citrate		0.2		0.2	0.2
<u>Total</u>	1.52g	1.683g	1.52g	1.683g	1.683g

<u>Organic solvent composition</u>					
MEA	10		4	5	5
MAE		10	4	5	
SF1488			4		5
<u>Total</u>	10 ml	10 ml	12 ml	10 ml	10 ml

Examples 6 to 10

- Examples 6 to 10 illustrate the use of a combination of an automatic dishwashing liquid detergent and an organic solvent composition for removing cooked-, baked- and burnt-on soils. The two-component compositions of examples 6 to 10 are used to wash a load of cookware and tableware according to the procedure described hereinabove (Examples 1 to 5). 30 ml of the dishwashing detergent and the 10 ml of the solvent composition are separately delivered to the main-wash cycle of a 5 litre liquor capacity Bosch 6032 dishwashing machine, at 55°C without prewash. The compositions of examples 6 to 10 provide excellent removal of cooked-on, baked-on and burnt-on food soils.

Example	6	7	8	9	10
<u>Dishwashing detergent composition</u>					
KOH	14.31	14.31	14.31	11.45	4.67
H ₂ SO ₄	11.26	11.26	11.26	9.00	
STPP	16.00	16.00	16.00	20.00	
SKTP					30.00
1,2-Propanediol	0.50	0.50	0.50	0.5	6.00
Boric acid	3.00	3.00	3.00	3.0	4.00
Polygel premix	24.40	24.40	24.40	24.00	24.40
PVPVI	0.02				
SLF18	1.0		1.0	1.00	
C ₁₆ AO	0.6	0.6		2.00	2.00

ACNI	0.3	0.3			3.00
CaCl ₂	0.04	0.04	0.04	0.37	0.37
Na benzoate	0.61	0.61	0.61	0.61	0.61
Proxel GXL	0.05	0.05	0.05	0.05	0.05
FN3	0.60	0.60	0.60	0.60	0.90
Duramyl	0.27	0.27	0.27		
Termamyl	0.3			0.17	0.26
Perfume	0.1	0.1	0.2	0.1	0.1
Dye	0.4	0.4	0.3	0.24	0.64
Water	26	27.22	24.46	26.91	23
<u>Organic solvent composition</u>					
MEA	100		33	50	50
MAE		100	33	50	
SF1488			34		50

Examples 11 to 15

Examples 11 to 15 further illustrate the use of a combination of an automatic dishwashing liquid detergent and an organic solvent composition for removing cooked-, baked- and burnt-on soils. The two-component compositions of examples 11 to 15 are used to wash a load of cookware and tableware according to the procedure described hereinabove (Examples 1 to 5). The automatic dishwashing liquid detergent and the organic solvent composition are delivered in separate compartments of a unit dose (30 ml of the dishwashing detergent and the 10 ml of the solvent composition) partially hydrolysed PVA water-soluble pouch. The pouch is delivered to the main-wash cycle of a Bosch 6032 dishwashing machine, at 55°C without prewash. The two-component compositions of examples 11 to 15 provide excellent removal of cooked-on, baked-on and burnt-on food soils. At the same time, they provide excellent compatibility with the PVA pouch material.

Example	11	12	13	14	15
<u>Dishwashing detergent composition</u>					
KOH	14.31	14.31	14.31	11.45	4.67
H ₂ SO ₄	11.26	11.26	11.26	9.00	
STPP	16.00	16.00	16.00	20.00	
SKTP					30.00
1,2-Propanediol	0.50	0.50	0.50	0.5	6.00
Boric acid	3.00	3.00	3.00	3.0	4.00
Polygel premix	24.40	24.40	24.40	24.00	24.40
PVPVI	0.02				
SLF18	1.0		1.0	1.00	
C ₁₆ AO	0.6	0.6		2.00	2.00
ACNI	0.3	0.3			3.00
CaCl ₂	0.04	0.04	0.04	0.37	0.37
Na benzoate	0.61	0.61	0.61	0.61	0.61
Proxel GXL	0.05	0.05	0.05	0.05	0.05
FN3	0.60	0.60	0.60	0.60	0.90
Duramyl	0.27	0.27	0.27		
Termamyl	0.3			0.17	0.26
Perfume	0.1	0.1	0.2	0.1	0.1
Dye	0.4	0.4	0.3	0.24	0.64
Water	26	27.22	24.46	26.91	23
<u>Organic solvent composition</u>					
MEA	50		20	30	30
MAE		50	20	30	
Benzyl alcohol	50	50	40	40	30
SF1488			20		40

Examples 16 to 19

Examples 16 to 19 illustrate the use of a combination of an automatic dishwashing liquid detergent and an organic solvent composition for removing cooked-, baked- and burnt-on soils. The two-component compositions are stored in a dual-compartment bottle having an electrically operated pump and delivered at a feed ratio (dishwashing liquid detergent:
 5 organic solvent composition) of 3:1. The compositions of examples 16 to 19 are used to wash a dishware load according to the procedure described hereinabove (Examples 1 to 5). 30 ml of the dishwashing detergent and 10 ml of the solvent composition are separately delivered from the dual-compartment bottle to the main-wash cycle of a Bosch 6032 dishwashing machine, at 55°C without prewash. The two-component compositions
 10 of examples 16 to 19 provide excellent removal of cooked-on, baked-on and burnt-on food soils.

Example	16	17	18	19
<u>Dishwashing detergent composition</u>				
STPP	28.00	28.00	28.00	28.00
KOH	5.30	5.30	5.30	5.30
Silicate 3.2	1.0	1.0	1.0	1.0
Polygel DKP	0.55	0.55	0.55	0.55
SLF18	1.25		1.25	
C ₁₆ AO		0.40		0.40
ACNI		3.00		3.00
Water				
<u>Organic solvent composition</u>				
MEA	75.56	75.56	37.78	37.78
MAE			37.78	37.78
PB1-50	18.5	18.5	18.5	18.5
FN3	2.60	2.60	2.60	2.60
Termamyl	3.34	3.34	3.34	3.34

Thickener	1.56	1.56	1.56	1.56
-----------	------	------	------	------

Examples 20 to 24

Examples 20 to 24 illustrate "all-in-one" solvent-containing automatic dishwashing detergent compositions. The compositions of examples 20 to 24 are used to wash a dishware load following the procedure described hereinabove (Examples 1 to 5). 40 ml of the dishwashing composition are delivered to the main-wash cycle of a Bosch 6032 dishwashing machine, at 55°C without prewash. The "all-in-one" compositions of examples 20 to 24 provide excellent removal of baked-on soils.

Example	20	21	22	23	24
<u>Dishwashing detergent solvent composition</u>					
KOH	4.60	5.65	2.10	1.47	1.05
H ₂ SO ₄	3.94	3.94			
MEA		4.00		4.00	8.00
STPP	22.00	22.00		22.00	22.00
SKTP			30.00		
1,2-Propanediol	0.5	0.5	6.00	5.5	5.5
Boric acid	3.00	3.00	4.00	3.4	3.4
Polygel premix	1.18	1.18	1.18	1.18	1.18
SLF18	1.0	1.0			
ACNI			3.0	2.1	2.1
C ₁₆ AO			0.40	0.308	0.308
CaCl ₂	0.2	0.2	0.22	0.2	0.2
Na benzoate	0.20	0.20	0.20	0.20	0.20
Proxel GXL	0.01	0.01	0.05	0.01	0.01
FN3	0.60	0.60	0.90	0.76	0.76
Duramyl	0.27				
Termamyl		0.17	0.26	0.23	0.23
Perfume	0.10	0.10	0.10	0.10	0.10

Dye	0.0024	0.0024	0.0024	0.0024	0.0024
Water					

Examples 25 to 28

Examples 25 to 28 illustrate pre-treatment compositions used to facilitate the removal of cooked-on, baked-on and burnt-on food soils prior to the dishwashing process. The compositions of examples 25 to 28 are applied to a dishware load having the soils described hereinabove (Examples 1 to 5). The dishware load is allowed to soak for 10 minutes, then the dishware is rinsed under cold tap water. The dishware load is thereafter washed either manually or in an automatic dishwashing machine, for example in a Bosch 6032 dishwashing machine, at 55°C without prewash, using the dishwashing detergent compositions of examples 1 to 5. The dishware load treated with compositions of examples 25 to 28 and thereafter washed in the dishwashing machines present excellent removal of cooked-on, baked-on and burnt-on food soils.

Example	25	26	27	28
<u>Pre-treatment composition</u>				
Butyl Carbitol	5.00	5.00	5.00	5.00
Dowanol PNB	5.00	5.00	5.00	5.00
MEA	5.00	5.00	5.00	5.00
Carbonate	2.00	2.00	2.00	2.00
C ₁₆ AO	3.00		1.5	1.5
SLF18		3.00		1.5
ACNI			1.5	
Polygel DKP	1.00	1.00	1.00	1.00
Water	79.00	79.00	79.00	79.00

Claims:

1. A method of removing cooked-, baked-, or burnt-on food soil from cookware and
5 tableware comprising washing the cookware/tableware in an automatic dishwashing
machine in the presence of an organic solvent system having a volatile organic content
of less than about 50% by weight and a wash liquor concentration of from about 100 to
about 5000 ppm.
- 10 2. A method of removing cooked-, baked-, or burnt-on food soil from cookware and
tableware comprising washing the cookware/tableware in an automatic dishwashing
machine in the presence of surfactant, detergency builder and an organic solvent
system having a volatile organic content of less than about 50% by weight, wherein
15 the surfactant, detergency builder and organic solvent system have a wash liquor
concentration of from about 10 to about 1000, about 100 to about 5000 and about 100
to about 5000 ppm respectively.
3. A method of removing cooked-, baked-, or burnt-on food soil from cookware and
tableware in an automatic dishwashing machine comprising delivering an organic
20 solvent composition in the pre-wash cycle of an automatic dishwashing machine and
thereafter delivering an automatic dishwashing detergent composition in the main-
wash cycle of the automatic dishwashing machine.
4. A method of removing cooked-, baked-, or burnt-on food soil from cookware and
25 tableware in an automatic dishwashing machine comprising delivering an organic
solvent composition and a first automatic dishwashing detergent composition in the
pre-wash cycle of an automatic dishwashing machine and thereafter delivering a
second automatic dishwashing detergent composition in the main-wash cycle of the
automatic dishwashing machine.
- 30 5. A method of removing cooked-, baked-, or burnt-on food soil from cookware and
tableware in an automatic dishwashing machine comprising delivering an organic

solvent composition and an automatic dishwashing detergent composition in the main-wash cycle of an automatic dishwashing machine.

- 5 6. A method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware in an automatic dishwashing machine comprising delivering an organic solvent composition and an automatic dishwashing detergent composition in the pre-wash and thereafter in the main-wash cycle of an automatic dishwashing machine.
- 10 7. A method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising washing the cookware/tableware in the pre-wash cycle of an automatic dishwashing machine in the presence of an organic solvent composition and thereafter rinsing the cookware/tableware in the rinse cycle of the automatic dishwashing machine in the presence of an automatic dishwashing rinse composition.
- 15 8. A method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising delivering an organic solvent composition and an automatic dishwashing detergent composition from separate storage means into the same cycle of an automatic dishwashing machine wherein the wash liquor concentration of organic solvent is in the range from about 100 to about 5000 ppm.
- 20 9. A method of washing cookware/tableware comprising delivering one or both of an organic solvent composition and an automatic dishwashing detergent composition contained in separate zones of a multi-zone storage means into the same or different cycles of an automatic dishwashing machine.
- 25 10. A method according to claim 9 for the removal of cooked-, baked-, or burnt-on food soil, the method comprising simultaneously delivering the organic solvent composition and automatic dishwashing detergent composition into the main wash cycle of the automatic dishwashing machine at a feed ratio (solvent composition: detergent composition) in the range from about 5:1 to about 1:50 to provide a wash liquor
30 concentration of organic solvent in the range from about 100 to about 5000 ppm.

11. A method according to claim 9 for the removal of cooked-, baked-, or burnt-on food soil, the method comprising sequentially delivering the organic solvent composition and automatic dishwashing detergent composition into the pre-wash and main-wash cycles respectively.
- 5
12. A method according to claim 9 wherein the multi-zone storage means is a multi-compartment container and wherein the physical form of the organic solvent composition and/or automatic dishwashing detergent compositions is such as to prevent intimate mixing of the compositions prior to contact thereof with the wash
- 10 liquor.
13. A method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising delivering separate portions of a multi-phase detergent composition into the same or different cycles of an automatic dishwashing machine,
- 15 wherein the multi-phase detergent composition comprises at least a first phase containing an organic solvent composition and at least a second phase containing an automatic dishwashing detergent composition.
14. A method of removing cooked-, baked-, or burnt-on food soil from cookware and
- 20 tableware comprising delivering a plurality of organic solvent compositions of different solvent characteristics into the same or different cycles of an automatic dishwashing machine.
15. A method according to claim 14 comprising delivering a first organic solvent
- 25 composition into the pre-wash cycle of the automatic dishwashing machine and a second organic solvent composition into the main wash cycle of the automatic dishwashing machine, and wherein the first and second organic solvent compositions have differing soil and/or substrate specificities.
- 30 16. A method according to claim 14 or 15 comprising delivering a first organic solvent composition and a first automatic dishwashing detergent composition in the pre-wash cycle and a second solvent composition and a second automatic dishwashing detergent composition in the main-wash cycle of the automatic dishwashing machine.

17. A method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising washing the cookware/tableware in an automatic dishwashing machine in the presence of an organic solvent composition and wherein the organic solvent composition is in a unit dose form adapted to provide controlled release of organic solvent during one or more repeated washing cycles.
18. A method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising washing the cookware/tableware in an automatic dishwashing machine with an automatic dishwashing detergent composition comprising surfactant (preferably comprising low-foaming nonionic surfactant), detergency builder and organic solvent system in levels sufficient to provide a wash liquor concentration of from about 10 ppm to about 1000 ppm surfactant, from about 100 ppm to about 5000 ppm detergency builder, and about 100 ppm to about 10,000, preferably from about 200 ppm to about 5000 ppm of organic solvent.
19. A method according to any preceding claim wherein the organic solvent composition is in the form of a liquid, paste, cream or gel which is optionally encapsulated, packaged in a single- or multi-compartment pouch, or absorbed onto a porous carrier material.
20. A method according to any preceding claim wherein the organic solvent system has a liquid surface tension of less than about 27 mN/m, preferably less than about 25 mN/m, or wherein the organic solvent system comprises a plurality of solvent components in levels such that the solvent system has a surface tension less than, and preferably at least 1 mN/m less than that of any of the individual solvent components.
21. A method according to any preceding claim wherein the composition comprising the organic solvent composition has an advancing contact angle on a polymerised grease-coated glass substrate of less than 20°, preferably less than 10° and more preferably less than 5°, and for mixed solvent systems is less than the advancing contact angle of

any of the corresponding compositions containing the individual components of the solvent system.

22. A method of removing cooked-, baked-, or burnt-on food soil from cookware and
5 tableware comprising treating the cookware/tableware with a hard surface cleaning
composition comprising an organic solvent system having a liquid surface tension of
less than about 27 mN/m.
23. A method according to claim 22 comprising the step of pre-treating the
10 cookware/tableware with the hard surface cleaning composition prior to manual or
automatic dishwashing.
24. A method according to any preceding claim wherein the organic solvent system is
selected from alcohols, amines, esters, glycol ethers, glycols, terpenes and mixtures
15 thereof.
25. A method according to any preceding claim wherein the organic solvent system is
selected from organoamine solvents, inclusive of alkanolamines, alkylamines,
alkyleneamines and mixtures thereof; alcoholic solvents inclusive of aromatic,
20 aliphatic (preferably C₄-C₁₀) and cycloaliphatic alcohols and mixtures thereof; glycols
and glycol derivatives inclusive of C₂-C₃ (poly)alkylene glycols, glycol ethers, glycol
esters and mixtures thereof; and mixtures selected from organoamine solvents,
alcoholic solvents, glycols and glycol derivatives.
- 25 26. A method according to claim 24 or 25 wherein the organic solvent comprises
organoamine (especially alkanolamine) solvent and glycol ether solvent, preferably in
a weight ratio of from about 3:1 to about 1:3, and wherein the glycol ether solvent is
selected from ethylene glycol monobutyl ether, diethylene glycol monobutyl ether,
ethylene glycol monomethyl ether, ethylene glycol monoethyl ether, diethylene glycol
30 monomethyl ether, diethylene glycol monoethyl ether, propylene glycol monobutyl
ether, dipropylene glycol monobutyl ether, ethylene glycol phenyl ether and mixtures
thereof.

27. A method according to any of claims 24 to 26 wherein the glycol ether is a mixture of diethylene glycol monobutyl ether and propylene glycol butyl ether, preferably in a weight ratio of from about 1:2 to about 2:1.
- 5 28. A method according to any of claims 24 to 27 wherein the organic solvent system comprises an organoamine solvent having a pKa of at least 8.8, preferably at least 9.3, more preferably at least 9.8.
- 10 29. A method according to any of claims 24 to 28 wherein the organic solvent system comprises a mixture of a first organoamine solvent having a pKa of 9.5 or less and a second organoamine solvent having a pKa greater than 9.5.
- 15 30. A method according to any of claims 24 to 29 wherein the organic solvent comprises one or more organoamines which is/are introduced into the wash liquor of an automatic dishwashing machine in the form their ammonium salt at a wash liquor pH above the highest pKa of the organoamine/s.
- 20 31. A method according to any preceding claim wherein the organic solvent system is used in conjunction with a wetting agent effective in lowering the surface tension of the solvent system, the wetting agent preferably being selected from organic surfactants having a surface tension less than about 30 mN/m, preferably less than about 28 mN/m, more preferably less than about 26 mN/m.
- 25 32. A method according to claim 31 wherein the wetting agent is selected from silicone polyether copolymers, especially silicone-poly(alkyleneoxide) copolymers.
- 30 33. A method according to any preceding claim wherein the organic solvent is essentially free of solvent components having a boiling point below about 150°C, flash point below about 100°C or vapor pressure above about 1 mm Hg.
34. A method according to any preceding claim wherein the organic solvent is selected from:

- a) polar, hydrogen-bonding solvents having a Hansen solubility parameter of at least 20 $(\text{Mpa})^{1/2}$, a polarity parameter of at least 7 $(\text{Mpa})^{1/2}$, preferably at least 12 $(\text{Mpa})^{1/2}$ and a hydrogen bonding parameter of at least 10 $(\text{Mpa})^{1/2}$
 - b) polar non-hydrogen bonding solvents having a Hansen solubility parameter parameter of at least 20 $(\text{Mpa})^{1/2}$, a polarity parameter of at least 7 $(\text{Mpa})^{1/2}$, preferably at least 12 $(\text{Mpa})^{1/2}$ and a hydrogen bonding parameter of less than 10 $(\text{Mpa})^{1/2}$
 - c) amphiphilic solvents having a Hansen solubility parameter below 20 $(\text{Mpa})^{1/2}$, a polarity parameter of at least 7 $(\text{Mpa})^{1/2}$ and a hydrogen bonding parameter of at least 10 $(\text{Mpa})^{1/2}$
 - d) non-polar solvents having a polarity parameter below 7 $(\text{Mpa})^{1/2}$ and a hydrogen bonding parameter below 10 $(\text{Mpa})^{1/2}$ and
 - e) mixtures thereof.
35. An automatic dishwashing detergent pack comprising two or more automatic dishwashing detergent or auxiliary products, storage means comprising separate but associated portions of the two or more products and means for delivering quantities of the two or more products into the same or different cycles of an automatic dishwashing machine.
36. An automatic dishwashing detergent pack comprising two or more automatic dishwashing detergent or auxiliary products, storage means comprising separate but associated portions of the two or more products, means for dispensing quantities of the two or more products, and means for controlling the relative dispensing rate of the two or more products from the storage means.
37. A pack according to claim 35 or 36 comprising an organic solvent composition and an automatic dishwashing detergent composition.
38. A pack according to any of claims 35 to 37 wherein the two or more automatic dishwashing detergent or auxiliary products are in rheology-matched gel-form.

39. A pack according to any of claims 35 to 38 for use in the method according to any of claims 1 to 34.
40. An organic solvent composition suitable for use in automatic dishwashing comprising
5 from about 1% to about 99%, preferably from about 5% to about 90%, especially from about 40% to about 80% of an organic solvent system for removing cooked-, baked-, or burnt-on food soil from cookware and tableware, from about 0.5% to about 50%, preferably from about 5% to about 25% of bleach, from about 0.0001% to about 10% of detergency enzyme, and wherein the composition is in the form of an anhydrous gel
10 comprising bleach in the form of a particulate suspension.
41. An automatic dishwashing detergent composition comprising from about 0.05% to about 10% by weight of a low-foaming non-ionic surfactant, from about 1% to about 30% of an organoamine, preferably alkanolamine solvent and at least about 5% by
15 weight of a detergency builder.
42. An automatic dishwashing detergent composition in the form of a gel comprising from about 2% to about 20%, preferably from about 5% to about 15% by weight of the composition of an alkanolamine, at least about 5% by weight of detergency builder,
20 and from about 0.1% to about 5% by weight of the composition of a low foaming non-ionic surfactant.
43. An automatic dishwashing detergent composition comprising from about 0.05% to about 10% by weight of a low-foaming non-ionic surfactant, from about 1% to about 30% of an organic solvent, preferably alkanolamine solvent, at least about 5% by
25 weight of a detergency builder and a wetting agent, preferably a silicone-poly(alkyleneoxide) copolymers.
44. An automatic dishwashing detergent pack according to any of claims 35 to 39
30 comprising the organic solvent composition of claim 40 and the automatic dishwashing detergent composition of any of claims 41 to 43.

45. A hard-surface cleaning or dishwashing pretreatment composition for removing cooked-, baked-, or burnt-on food soil from cookware and tableware, the composition comprising an organic solvent system having a liquid surface tension of less than about 27 mN/m, preferably less than about 26 mN/m, the composition being in the form of a liquid or gel having a pH of greater than about 10.5, preferably greater than about 11.
46. A hard-surface cleaning or dishwashing pretreatment composition for removing cooked-, baked-, or burnt-on food soil from cookware and tableware, the composition comprising an organic solvent system having an advancing contact angle on polymerised grease-coated glass substrate of less than 20°, preferably less than 10° and more preferably less than 5°.
47. A hard-surface cleaning or dishwashing pretreatment composition for removing cooked-, baked-, or burnt-on food soil from cookware and tableware, the composition comprising an organic solvent system comprising a plurality of solvent components in levels such that the solvent system has an advancing contact angle on polymerised grease-coated glass substrate of less than that of corresponding compositions containing the individual components of the solvent system.
48. A hard-surface cleaning or dishwashing pretreatment composition for removing cooked-, baked-, or burnt-on food soil from cookware and tableware according to any of claims 45 to 47 wherein the composition is in the form of a shear thinning fluid having a shear index from about 0.3 to about 0.7, preferably from about 0.4 to about 0.6 and a consistency index from about 0.20 to about 0.15, preferably from about 0.175 to about 0.160 kg/(m s²⁻ⁿ).
49. A composition according to any of claims 40 to 48, the composition having a volatile organic content above 0.1 mm Hg of less than about 20%, preferably less than about 10% and more preferably less than about 5% by weight of the composition.

50. Use of an organic solvent system in an automatic dishwashing machine to remove cooked-, baked-, or burnt-on food soil from cookware and tableware.

ABSTRACT

A method of removing cooked-, baked-, or burnt-on food soil from cookware and tableware comprising washing the cookware/tableware in an automatic dishwashing machine in the presence of an organic solvent system having a wash liquor concentration of from about 100 to about 5000 ppm. The method includes the storage and delivery of organic solvent compositions and dishwashing detergent composition from multi-compartment containers. The method provides excellent removal of stubborn soils which are very difficult to remove in a conventional automatic dishwashing process. Automatic detergent dishwashing compositions and hard-surface detergent compositions comprising organic solvent systems for the removal of cooked-, baked-, or burnt-on food soil from cookware and tableware are also disclosed.

PATENT COOPERATION TREATY

From the RECEIVING OFFICE

PCT

To:

T. DAVID REED
THE PROCTER & GAMBLE COMPANY
5299 SPRING GROVE AVENUE
CINCINNATI OH 45217-1087

NOTIFICATION OF THE INTERNATIONAL
APPLICATION NUMBER AND OF THE
INTERNATIONAL FILING DATE

(PCT Rule 20.5(c))

Date of mailing
(day/month/year)

10 AUG 2000

Applicant's or agent's file reference
CM2399F/JH

IMPORTANT NOTIFICATION

International application No.

PCT/US00/19619

International filing date (day/month/year)

19 JUL 00

Priority date (day/month/year)

Applicant THE PROCTER & GAMBLE COMPANY

Title of the invention CLEANING COMPOSITION

1. The applicant is hereby notified that the international application has been accorded the international application number and the international filing date indicated above.

2. The applicant is further notified that the record copy of the international application:



was transmitted to the International Bureau on

10 AUG 2000



has not yet been transmitted to the International Bureau for the reason indicated below and a copy of this notification has been sent to the International Bureau**.



because the necessary national security clearance has not yet been obtained.



because (reason to be specified):

* The International Bureau monitors the transmittal of the record copy by the receiving Office and will notify the applicant (with Form PCT/IB/301) of its receipt. Should the record copy not have been received by the expiration of 14 months from the priority date, the International Bureau will notify the applicant (Rule 22.1(c)).

3. FOREIGN TRANSMITTAL LICENSE INFORMATION

Completed by:

[Signature]



Additional license for foreign transmittal not required. This subject matter is covered by a license already granted on the equivalent U.S. national application. Refer to that license for information concerning its scope.



License for foreign transmittal not required. 37 CFR 5.11(e)(1) or 37 CFR 5.11(e)(2). However, a license may be required for additional subject matter. See 37 CFR 5.15(b).



Foreign transmittal license granted. 35 U.S.C. 184; 37 CFR 5.11 on

8-2-00.
(date)



37 CFR 5.15(a)



37 CFR 5.15(b)

Name and mailing address of the receiving Office
Assistant Commissioner for Patents
Box PCT
Washington, D.C. 20231

Attn: RO/US

Facsimile No.

Authorized officer

Felicia Lawrence

PCT Operations - IAPD Team 1

(703) 305-3675 (703) 305-3230 (FAX)

Telephone No.

PCT APPLICATION NUMBER: 00/19619

T. DAVID REED
THE PROCTER & GAMBLE COMPANY
5299 SPRING GROVE AVENUE
CINCINNATI OH 45217-1087